FORM OF TENDER.

Tender for carting and the supply of miscellaneous articles required by the Government Stationery Depot for the year 1936-37.

Earnest money (Rs. 50).

SCHEDULE.

No.	Description of articles	Approximate quantity required	Per	Rate
				Rs. a. p.
1*	Dealwood boxes large 3′×2′—5″×1′—10″ ..	75	each	
2*	Do small 2′—10″×2′—2″×1′—6″ ..	75	,,	
3	Wire nails of sizes	50 lbs.	lb.	
4	Country gum	20 seers	seer	
5	Pin sheets, in two sizes of ¾″ and 1″ ..	36	sheet	
6	Naphthalene balls	3 lbs.	lb.	
7	Match boxes	5 dozens	dozen	
8	Carting—			
	Cases	150	each	
	Bales	1,000	,,	
	Bundles	1,500	,,	
9	Self-inking stamp pads 'Excelsior No. 1'	1 dozen	,,	
10	Ink phials (blue) for the above	1 ,,	,,	
11	Packing twine	10 maunds	maund	
12	Gunny sheets, 40″ wide in rolls of 100 yards† ..	10 rolls	roll	
13	Tar	5 maunds	maund	
14	Saw dust	5 bags of standard size.	bag	

* Boxes that are not up to measurement will be rejected.

† Samples to be furnished.

Tenderer.

GOVERNMENT OF MYSORE, ELECTRICAL DEPARTMENT.

CHIEF ELECTRICAL ENGINEER'S OFFICE.

Abstract Notification dated 16th April 1936.

Tenders will be received in the Office of the Executive Engineer, Sivasamudram, up to 2 P.M., on the 12th May 1936 for different items of works connected with IX Installation Works at Sivasamudram.

For further particulars, *vide* pages 571-573, Part VI of the *Mysore Gazette*, dated the 23rd April 1936.

Notification dated the 30th April 1936.

1. Sealed tenders will be received at the Office of the Chief Electrical Engineer in Mysore, Bangalore, for the following material, up to 12 noon on Saturday the 23rd May 1936. The covers containing the tenders should bear the superscription "Quotation to be opened at 12 noon, on 23rd May 1936."

800—ft. of varnished cambric insulated, lead-sheathed, jute served and double weather-proof braided, single conductor, No. 2 B. and S. stranded cable, suitable for out-door use for a working pressure of 6,000-volts A.C.

The thickness of the varnished cambric insulation should be not less than 10/64″ and that of the lead sheath 1/16″.

The conductors should be composed of high conductivity annealed copper and the finished cable should conform to the latest B.E.S.A. or A.I.E.E. standards in other respects.

The cable should also be tested according to any one of the abovementioned standards and test reports submitted to us.

The time required for supplying the material should be definitely mentioned.

2. Any further particulars the tenderers may require may be had on application to the Chief Electrical Engineer.

Abstract Notification dated 27th April 1936.

The attention of the public is invited to the detailed notification, published in the *Mysore Gazette*, dated 30th April 1936, Part VI, pages 617-618, calling for quotation in connection with the work of strengthening the Bund and Weir of Silt Reservoir at Sivasamudram, due on 16th May 1936 at the Office of the Executive Engineer, C.P.S., Sivasamudram up to 2 P.M.

M. HAYATH,
For *Chief Electrical Engineer.*

OFFICE OF THE SUPERINTENDENT, BANGALORE POWER AND LIGHTING, BANGALORE.

Notice.

The attention of the public is invited to the detailed notification published in the *Mysore Gazette*, dated 30th April 1936, Part VI, page 616, regarding auctioning of empty teakwood cut out boxes, etc., on 18th May 1936, between 2 and 5 P.M. in the premises of the Bangalore Power and Lighting Stores, situated in the compound of Central Industrial Workshop.

C. R. GOWDA,
Superintendent.

OFFICE OF THE EXECUTIVE ENGINEER, C.P.S., SIVASAMUDRAM.

Notification dated 25th April 1936.

Notice is hereby given that quotations will be received from piece work contractors at the Office of the Executive Engineer, C.P.S., Sivasamudram, up to 2 P.M., on Saturday the 9th May 1936, for construction of temporary quarters for the staff at Sivasamudram. An approximate estimate of quantities is given below. These quantities are not guaranteed.

The work entrusted to any contractor should be completed within one month. If the progress of work of any contractor is not found satisfactory, his contract will be cancelled by the Executive Engineer, without notice after withholding such penalty as may be fixed by the Executive Engineer, at the time of drawing up the agreement.

2. The plans, detailed estimates and conditions may be seen at the Office of the Executive Engineer, during the working hours on any working day.

3. Quotations may be submitted on printed forms, which may be obtained from the Executive Engineer. Quotations may be submitted for each block of quarters separately, as the work is proposed to be got executed by piecework agency through several contractors.

4. The final acceptance of the quotation of any pieceworker will rest with the Executive Engineer, who is not bound to accept the lowest or any quotation or to assign any reason whatever for the rejection of any tender. The Executive Engineer may accept or reject part or whole of any one quotation.

5. Immediately on acceptance of any quotation or part thereof, the piecework contractor will be bound to deposit as earnest money 5 per cent of the value of work entrusted to him. The earnest money will be refunded only after the settlement of the final claims of the contractor. Whenever the rate of progress or quality of work is not satisfactory, a penalty as may be specified by the Executive Engineer in the agreement will be levied which will be deducted either from the bills or earnest money.

6. Rates for non-quoted and non-estimated items will be fixed by the Executive Engineer from time to time.

7. Quotations should be submitted quoting rates for each item of work in any one building or a lumpsum rate for a whole building. In the latter case, the items of "Electric Lighting and Water Supply and maintenance charges for two years" provided in the estimate should be excluded.

8. The rates and units should be mentioned clearly in words. Any quotation quoted at so much percentage less or more than the estimated rate will not be accepted.